



- DALI Hub For Connection of up to 128 Addresses
- Built in accordance with IEC 62386-202
- Low Power Consumption
- Features Power Isolation for Maintenance
- Can be Connected in Multiple Arrangements
- For use with all Liteplan Controls' Systems

The MHUB is designed as a wall mounted, modular enclosure which can be mounted together for larger networks. The enclosure is installer friendly with many knock outs for mounting and cable entry.

The Monitor MHUB will operate up to 128 DALI addresses over two DALI buses. The units can be connected to form a network of up to ten enclosures, which could operate up to 1,280 fittings.

There is one version available -

Order Codes

MHUB/2DALI/ENC1/SW	Modular enclosure containing 1No. 2 Channel DALI hub with 5 port un managed network switch.
--------------------	---

Technical Details:

Mains Supply	230-240V AC 50/60 Hz
Power Rating	26mA $\lambda = 0.88$
Temperature Parameters (Ta)	0 °C to 35 °C
Electrical Connection	Permanent Mains Supply to Fused Terminal Block Accepting 1.0 to 2.5mm cable.
Ethernet Connector	RJ45
Overall Dimensions	300mm wide x 300mm high x 90mm deep
Cable Entry Choices	R10 and R12.5